
# Lot Line Amendment MAJESTIC HEIGHTS SUBDIVISION NO. 6 Lots 153 and 154

A PART OF THE NORTHEAST QUARTER OF SECTION 19
AND A PART OF THE NORTHWEST QUARTER OF SECTION 20,
TOWNSHIP 7 NORTH, RANGE 1 WEST, SLB&M
PLEASANT VIEW CITY, WEBER COUNTY, UTAH
NOVEMBER, 2007



# PLEASANT VIEW ENGINEER

I hereby certify that all applicable statutes and ordinances prerequisite to city engineer of the foregoing plat and dedications have been complied with.

Signed this \_\_\_\_\_day of \_\_\_\_\_,2007.

# PLEASANT VIEW CITY ACCEPTANCE

This is to certify that this lot line amendment was duly approved and accepted by the city council of pleasant View City, Utah.

this \_\_\_\_\_day of \_\_\_\_\_ 2007

Mayor

# PLEASANT VIEW PLANNING COMMISSION ACCEPTANCE

This is to certify that this lot line amendment was duly approved by the Pleasant View City Planning Commission on the \_\_\_\_\_ day of \_\_\_\_\_2007.

Chairman, Pleasant View City Planning Commission

### SURVEYORS CERTIFICATE

I, K. Greg Hansen, a registered land surveyor in the State of Utah, do hereby certify that this plat of LOT LINE AMENDMENT TO LOTS 153 AND 154, MAJESTIC HEIGHTS SUBDIVISION NO. 6, located in North Ogden, Weber County, Utah has been correctly drawn to the designated scale and is a true and correct representation of the following description of lands included in said subdivision, based on data compiled from records in the Weber County Recorders Office, and of a survey made on the

ound.	•	
gned thisday of	, 2006	William Control of the Control of th
		167819
		MEDITE GREG
	K. Greg Hansen	HANSEN OF THE STATE OF THE STAT
		Manne Market Comments of the Comment

#### Subdivision Boundary Description

A PART OF THE NORTHEAST QUARTER OF SECTION 19 AND A PART OF THE NORTHWEST QUARTER OF SECTION 20, TOWNSHIP 7 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN.

BEGINNING AT THE SOUTHWEST CORNER OF LOT 153, MAJESTIC HEIGHTS SUBDIVISION NO. 6;

RUNNING THENCE NORTH 75°29'15" EAST 217.74 FEET TO THE NORTHWEST CORNER OF SAID LOT 153

AND THE SOUTH RIGHT—OF—WAY LINE OF 4075 NORTH STREET; THENCE ALONG SAID RIGHT—OF—WAY LINE THE FOLLOWING THREE (3) COURSES; (1) TO THE LEFT ALONG THE ARC OF A 50.00 FOOT RADIUS CURVE, A DISTANCE OF 80.83 FEET, CHORD BEARS SOUTH 60°49'31" EAST 72.31 FEET; (2) TO THE RIGHT ALONG THE ARC OF A 30.00 FOOT RADIUS CURVE, A DISTANCE OF 21.68 FEET, CHORD BEARS SOUTH 86°26'00" EAST 21.21 FEET; (3) SOUTH 65°43'43" EAST 108.10 FEET; THENCE TO THE RIGHT ALONG THE ARC OF A 15.00 FOOT RADIUS CURVE, A DISTANCE OF 21.42 FEET, CHORD BEARS SOUTH 24°49'36" EAST 19.64 FEET TO THE WEST RIGHT—OF—WAY LINE OF 300 WEST STREET; THENCE ALONG SAID WEST RIGHT—OF—WAY LINE THE FOLLOWING TWO (2) COURSES; (1) SOUTH 16°04'30" WEST 86.02 FEET; (2) TO THE RIGHT ALONG THE ARC OF A 1365.70 FOOT RADIUS CURVE, A DISTANCE OF 40.04 FEET, CHORD BEARS SOUTH 16°54'54" WEST 40.04 FEET TO THE SOUTHEAST CORNER OF SAID LOT 154; THENCE NORTH 65°43'43" WEST 40.04 FEET TO THE SOUTH LINE OF SAID LOT 154; THENCE NORTH 65°43'43" WEST 40.06 FEET ALONG THE SOUTH LINE OF SAID LOT 154 AND THEN SAID LOT 153 TO THE POINT OF BEGINNING.

CONTAINING 0.943 ACRES AND TWO LOTS.

#### Lot 14

A PART OF THE NORTHEAST QUARTER OF SECTION 19 AND A PART OF THE NORTHWEST QUARTER OF SECTION 20, TOWNSHIP 7 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN.

BEGINNING AT THE SOUTHWEST CORNER OF LOT 153, MAJESTIC HEIGHTS SUBDIVISION NO. 6;

RUNNING THENCE NORTH 75°29'15" EAST 217.74 FEET TO THE NORTHWEST CORNER OF SAID LOT 153

AND THE SOUTH RIGHT—OF—WAY LINE OF 4075 NORTH STREET; THENCE ALONG SAID RIGHT—OF—WAY

LINE TO THE LEFT ALONG THE ARC OF A 50.00 FOOT RADIUS CURVE, A DISTANCE OF 80.83 FEET,

CHORD BEARS SOUTH 60°49'31" EAST 72.31 FEET; THENCE SOUTH 19°39'06" WEST 130.62 FEET TO

THE SOUTHEAST CORNER OF SAID LOT 153; THENCE NORTH 65°43'43" WEST 252.30 FEET ALONG THE

SOUTH LINE OF SAID LOT 153 TO THE POINT OF BEGINNING.

CONTAINING 0.484 ACRES.

#### Lot 14

A PART OF THE NORTHEAST QUARTER OF SECTION 19 AND A PART OF THE NORTHWEST QUARTER OF SECTION 20, TOWNSHIP 7 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN.

BEGINNING AT THE SOUTHEAST CORNER OF LOT 154, MAJESTIC HEIGHTS SUBDIVISION NO. 6;

RUNNING THENCE NORTH 65°43'43" WEST 149.66 FEET ALONG THE SOUTH LINE OF SAID LOT 154;

THENCE NORTH 19°39'08" EAST 130.62 FEET TO THE SOUTH RIGHT—OF—WAY LINE OF 4075 NORTH

STREET; THENCE ALONG SAID RIGHT—OF—WAY LINE THE FOLLOWING TWO (2) COURSES; (1) TO THE

RIGHT ALONG THE ARC OF A 30.00 FOOT RADIUS CURVE, A DISTANCE OF 21.68 FEET, CHORD BEARS

SOUTH 86°26'00" EAST 21.21 FEET; (2) SOUTH 65°43'43" EAST 108.10 FEET; THENCE TO THE RIGHT

ALONG THE ARC OF A 15.00 FOOT RADIUS CURVE, A DISTANCE OF 21.42 FEET, CHORD BEARS SOUTH

24°49'36" EAST 19.64 FEET TO THE WEST RIGHT—OF—WAY LINE OF 300 WEST STREET; THENCE ALONG

SAID WEST RIGHT—OF—WAY LINE THE FOLLOWING TWO (2) COURSES; (1) SOUTH 16°04'30" WEST

86.02 FEET; (2) TO THE RIGHT ALONG THE ARC OF A 1365.70 FOOT RADIUS CURVE, A DISTANCE OF

40.04 FEET, CHORD BEARS SOUTH 16°54'54" WEST 40.04 FEET TO THE POINT OF BEGINNING.

CONTAINING 0.459 ACRES.

#### OWNERS SIGNATURES

Stanley L. Weeks	William H. Joy
	Frances K. Joy

#### NARRATIVE:

The purpose of this survey was to establish the amended lot line common to lots 153 and 154, Majestic Heights Subdivision No. 6 as shown and described hereon to give an additional property to the original Lot 153. The Survey was ordered by Stan Weeks, owner of Lot 153. The basis of bearing is the Center line of 4050 North Street running West of 300 East Street which bears N 65°43'13" W.

## 004055

RECEIVED
MAY 1 9 2008
WEBER CO SURVEYO

# ACKNOWLEDGMENT

State of Utah County of Weber	
indersigned Notary Public,	, 2007, personally appeared before me the the signers of the above Lot Line Amendment, wledged to me that they signed it freely and bose therein mentioned.

COUNTY REC	
ENTRY NO	FEE P
FILED FOR	RECORD A
RECORDED	
IN BOOK	OF OFFI
RECORDS. PAGE	

	COUNTY RECURDER
BY _	
	DEPUTY

07-3-194 07-3-194 NEW.DWG 11/06/07