

## NARRATIVE

This survey was ordered by International Land Surveying, Inc. Monuments were found for the West line of Section 13, T5N, R2W, SLB & M and were used as the basis of bearings.

Monuments found and Set are as depicted on this drawing.

## SURVEYOR'S CERTIFICATE

NOVEMBER 30, 1994

The undersigned, being a duly licensed and qualified surveyor in and for the State of Utah, does hereby certify to;

WHLN Real Estate Limited Partnership, a Delaware Limited Partnership, Safeco Title Insurance Company, Founders Title Company and

that this survey print is a true and accurate survey based on an inspection of the following described real estate;

## EXHIBIT 'A' Legal Description

PARCEL 1: Part of the Southwest Quarter of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian: BEGINNING on the East line of U.S. Highway 91 (1900 West Street) at a point North 0°04'22" West along the Section Line 858.00 feet and East 50.00 feet from the Southwest Corner of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian, in Roy, Utah and running thence North 0°04'22" West along East line 897.56 feet to a point of a 523.00 foot radius curve to the right; thence Northeasterly along the arc of said curve through a central angle of 52°14'00" a distance of 476.79 feet to a point of langency on the Southerly line of Riverdale Road; thence North 52°09'38" East along the Southerly line 307.33 feet; thence South 37°50'22" East 175.0 feet; thence South 52°09'38" West 19.04 feet; thence South 36°26'22" East 49.96 feet; thence North 73°42'38" East 138.79 feet to the Westerly line of the Union Pacific Railroad right of way; thence South 12°43'04" West along said Westerly line 902.87 feet, more or less, ( 908.72 feet calculated to close ) to the South line of the Northwest Quarter of the Southwest Quarter of said Section 13; thence East along said South line 39.98 feet; thence South 12°43'04" West along said Westerly right of way line 473.84 feet; thence West 434.55 feet to the point of BEGINNING.

FXCEPTING FROM THE ABOVE TRACT. THE FOLLOWING 5 PARCELS:

PAD C: Part of the Southwest Quarter of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian: BEGINNING on the East line of U.S. Highway 91 (1900 West Street) a point North 0°04'22" West along the Section line 1472.84 feet and East 50.00 feet from the Southwest Corner of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian, in Roy, Utah and running thence North 0.04.22" West along said East line 282.72 teet to a point of a 523.0 foot radius curve to the right; thence Northeasterly along the arc of a said curve through a central angle of 29°02' a distance of 265.02 feet; thence South 73°29'45" East 151.02 feet; thence North 52°09'38" East 108.22 feet; thence South 37°50'22" East 197.16 feet; thence South 12°43'04" West 38.00 feet; thence South 77°16'56" East 85.00 feet: thence North 26°15' East 101.74 feet; thence South 63°45' East 97.91 feet to the Westerly line of the Salt Lake and Ogden Railroad right of way; thence South 12°43'04" West along said Westerly line 531.00 feet; thence West 76.98 feet; thence North 0°04'22" West 148.64 feet; thence North 77°16'56" West 96.00 feet; thence South 12°43'04" West 73.16 feet; thence West 119.76 feet; thence North 0°04'22" West 23.00 feet; thence West 200.00 feet to the point of BEGINNING.

PAD H: Part of the Southwest Quarter of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian: BEGINNING on the Southerly line of Riverdale Road at a point North 0°04'22" West along the Section line of 2252.07 feet and East 359.41 feet from the Southwest Corner of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian, in Roy, Utah and running thence North 52°09'38" East along said Southerly line 172.33 feet; thence South 37°50'22" East 175.00 feet; thence South 52°09'38" West 172.33 feet; thence North 37°50'22" West 175.00 feet to the point of

PAD L: Part of the Southwest Quarter of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian: BEGINNING on the East line of U.S. Highway 91 (1900 West Street) at a point North 0°04'22" West along the Section line 1182.00 feet and East 50.00 feet from the Southwest Corner of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian, in Roy, Utah, and running thence North 0°04'22" West along said East line 112.84 feet; thence East 200.00 feet; thence South 0°04'22" East 112.84 feet; thence West 200.00 feet to the point of BEGINNING.

PAD M: Part of the Southwest Quarter of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian: BEGINNING on the East line of U.S. Highway 91 (1900 West Street) at a point North 0°04'22" West along the Section line 1022.0 feet and East 50.00 feet from the Southwest Corner of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian, in Ray, Utah, and running thence North 0°04'22" West along said East line 160.0 feet; thence East 200.00 feet; thence South 0°04'22" East 160.00 feet; thence West 200.00 feet to the point of BEGINNING.

PAD N: Part of the Southwest Quarter of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian: BEGINNING on the East line of U.S. Highway 91 (1900 West Street) at a point North 0°04'22" West along the Section line 858.00 feet and East 50.00 feet from the Southwest Corner of Section 13, Township 5 North, Range 2 West, Salt Lake Base and Meridian, in Roy, Utah, and running thence North 0°04'22" West along said East line 164.00 feet; thence East 160.00 feet; thence South 0°04'22" East 164.00 feet; thence West 160.00 feet to the point of BEGINNING.

containing 8.072 acres and 351,636 square feet.

1. I further certify that this map or plat and the survey on which it is

- (a) in accordance with the "Minimum Standard Detail Requirements for ALTA/ACSM Land Title Surveys", jointly established and adopted by ALTA and ACSM in 1992, and includes items 1,2,3,4,6,7,8,9,10,11 and 13 of Table A thereof:
- (b) pursuant to the Accuracy Standards (as adopted by ALTA and ACSM and in effect on the date of this certification) of an "Urban" Surveyl: and
- (c) meets the current minimum standard requirements for the State of
- 2. I further certify;
  - (a) that this survey was prepared by me and was actually made on the ground and the instrumentation and field procedures utilized in the preparation of this survey were by field crew and total station and that a minimum linear closure of 1:15000 was obtained and that the survey reflects boundary lines of the described land which create a mathematically closed figure:
  - (b) that there are no discrepancies between the boundary lines of the subject property as shown on the survey map and as described in the legal description of record, except as specifically shown on this survey print;
  - (c) that the information, courses and distances shown on this survey print are correct and accurately represent the boundaries and area
  - of the premises; (d) that the title lines shown on this survey print and the lines of actual possession are the same;
  - (a) that it shows a fixed and determinable position and location of the Premises (including the position of the point of beginning);
  - (f) that the boundary lines of the subject property are contiguous with the boundary lines of all adjoining parcels, roads, highways, streets or alleys as described in their most recent respective legal descriptions of record:
- 3. I further certify;
  - (a) that the survey accurately reflects the location, width and recording data of all easements, rights-of-way, setback or building restriction lines and other matters observable by or known to the undersigned;
  - (b) that there is no observable evidence of easements, servitudes, rights of way, paths, party walls, or uses affecting the Premises that would be visible by a careful physical inspection of the Premises, or that are known by the undersigned, other than those
  - (c) that the survey accurately reflects the location, width and recording data of all setback or building restriction lines;
- 4. I further certify that the survey accurately shows the location, dimensions and types of all;
  - (a) existing buildings, structures, and other improvements situated on the Premises and the distances from each building to the nearest facing exterior property line, to building setback lines, if applicable, and to adjacent buildings on the Premises;
  - (b) driveways or other curb cuts along any abutting streets and the width of the abutting streets:
  - that all parking areas and the number of parking spaces have been accurately located and stated hereon;
  - (d) storm drainage systems, and the direction thereof, for the collection and disposal of all observable surface drainage;
  - utility services for the Premises that are observable by or known to the undersigned and whether they enter the Premises through adjoining public streets and easements, or the point of entry and location of such utilities which pass through or are located on adjoining private land (ABSENCE OF UTILITIES SHALL BE SPECIFICALLY
  - (f) utility transformers located on the Premises;
- 5. I further certify that, except as specifically shown;
  - (a) there are no party walls, protrusions, encroachments or overhangs on adjoining premises, streets, alleys by any of said buildings, structures or other improvements situated on the Premises;
  - (b) there are no party walls, protrusions, encroachments or overhangs on easements or rights-of-way observable by or known to the undersigned by any of said buildings, structures or other improvements situated on the Premises:
  - there are no encroachments, protrusions or overhangs on the Premises by buildings, structures or other improvements situated on adjoining premises;
  - (d) there are no easements, rights-of-way, servitudes, uses, roads, sidewalks, drainage ways, streams, rivers, waterways, ditches, springs, ponds, lakes or drainage located on, running across or affecting the Premises that would be visible by a careful inspection of the Premises, or that are known by the undersigned;
  - (e) no part of the surveyed property serves any adjoining property, street or alley for drainage, ingress, egress or similar purposes;
  - 6. I further certify that ingress and egress to the Premises is provided by U.S. Highway 91 (1900 West Street) and Riverdale Road upon which the Premises abuts, the same being a paved and dedicated right of way maintained by Utah State and Roy City.

Surveyor Title Block

Date 6 Dec, 1994

ILS2


1" = 40'

Dwn. By

Aprvd. By

Dwg. No.

Newman, Utah L.S. #4778



Sheet

4

Roy, Weber County, Utah

Lincoln Project Roy Marketplace Plaza