

ALTA/ACSM LAND TITLE SURVEY

LOCATED IN THE SOUTHWEST QUARTER OF SECTION 5, TOWNSHIP 5 NORTH, RANGE 1 WEST, SALT LAKE BASE AND MERIDIAN SOUTH OGDEN CITY, WEBER COUNTY, UTAH





IE(NE)=4371.25

HZ PROPS UT. LLC: FOUNDERS TITLE COMPANY: COMMONWEALTH LAND TITLE INSURANCE COMPANY:

> THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2011 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/ACSM LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS. AND INCLUDES ITEMS 2, 4, 5, 8, 11(b), AND 13 OF TABLE A THEREOF. THE FIELDWORK WAS COMPLETED ON DECEMBER 13, 2014.



TITLE DESCRIPTIONS:

PART OF LOT 3, BLOCK 1, BURCH ADDITION, OGDEN CITY, WEBER COUNTY, UTAH: BEGINNING AT THE NORTHWEST CORNER OF SAID LOT 3; RUNNING THENCE SOUTH 50 FEET TO THE SOUTHWEST CORNER OF SAID LOT 3; THENCE EAST ALONG THE SOUTH LINE OF SAID LOT 3 A DISTANCE OF 60 FEET: THENCE NORTHERLY 50 FEET TO THE SOUTHEAST CORNER OF LOT 15, SAID BLOCK 1; THENCE WESTERLY 60 FEET TO THE PLACE OF BEGINNING.

ALL OF LOT 4, BLOCK 1, BURCH ADDITION TO SOUTH OGDEN, ACCORDING TO THE OFFICIAL PLAT THEREOF ON FILE AND OF RECORD IN THE OFFICE OF THE WEBER COUNTY RECORDER.

LESS AND EXCEPTING:

A PARCEL OF LAND IN FEE, BEING A PART OF AN ENTIRE TRACT OF PROPERTY, IN A PORTION OF LOT 4, BLOCK 1, BURCH ADDITION, A SUBDIVISION SITUATE IN THE SE1/4SW1/4 OF SECTION 5, T.5N., R.1W., S.L.B.&M. THE BOUNDARIES OF SAID PARCEL OF LAND ARE DESCRIBED AS

BEGINNING AT THE INTERSECTION OF THE NORTHERLY BOUNDARY LINE OF SAID LOT 4 AND THE NORTHWESTERLY RIGHT OF WAY LINE OF THE EXISTING HIGHWAY STATE ROUTE 26, SAID INTERSECTION IS ALSO APPROXIMATELY 50.50 FEET PERPENDICULARLY DISTANT NORTHWESTERLY FROM THE CONTROL LINE OF SAID PROJECT SP-0026(4)0 OPPOSITE ENGINEER STATION 175+49.79, AND RUNNING THENCE S. 38°18'59" W. 57.98 FEET (S. 38°21'00" W 58.00 FEET BY RECORD) ALONG SAID RIGHT OF WAY LINE TO THE SOUTHERLY BOUNDARY LINE OF SAID LOT 4: THENCE N. 84°07'00" W. 7.39 FEET ALONG SAID SOUTHERLY BOUNDARY LINE TO A POINT 56.48 FEET PERPENDICULARLY DISTANT NORTHWESTERLY FROM SAID CONTROL LINE; THENCE N. 38°32'57" E. 58.13 FEET TO SAID NORTHERLY BOUNDARY LINE AT A POINT 56.48 FEET PERPENDICULARLY DISTANT NORTHWESTERLY FROM SAID CONTROL LINE; THENCE S. 84°07'00" E. 7.11 FEET ALONG SAID NORTHERLY BOUNDARY LINE TO THE POINT OF BEGINNING AS SHOWN ON THE OFFICIAL MAP OF SAID PROJECT ON FILE IN THE OFFICE OF THE UTAH DEPARTMENT OF TRANSPORTATION.

ALL OF LOTS 10 AND 11, BLOCK 1, BURCH ADDITION TO SOUTH OGDEN, ACCORDING TO THE OFFICIAL PLAT THEREOF ON FILE AND OF RECORD IN THE OFFICE OF THE WEBER COUNTY RECORDER.

ALL OF LOTS 12, 13, 14 AND 15, BLOCK 1, BURCH ADDITION TO SOUTH OGDEN, ACCORDING TO THE OFFICIAL PLAT THEREOF ON FILE AND OF RECORD IN THE OFFICE OF THE WEBER COUNTY RECORDER.

AS-SURVEYED DESCRIPTION:

BEGINNING AT A POINT WHICH IS ON THE WESTERLY RIGHT-OF-WAY LINE OF RIVERDALE ROAD (SR-26), SAID POINT ALSO BEING ON THE NORTH LINE OF LOT 4, BURCH ADDITION, ON FILE WITH THE OFFICE OF THE WEBER COUNTY RECORDER, SAID POINT ALSO BEING SOUTH 00°58'00" WEST ALONG THE MONUMENT LINE OF LINCOLN AVENUE A DISTANCE OF 1047.82 FEET AND SOUTH 38°21'00" WEST ALONG THE MONUMENT LINE OF RIVERDALE ROAD A DISTANCE OF 657.46 FEET FROM THE MONUMENT FOUND MARKING THE INTERSECTION OF LINCOLN AVENUE AND 36TH STREET, AND RUNNING THENCE SOUTH 38°36'22" WEST ALONG SAID RIGHT-OF-WAY LINE A DISTANCE OF 58.14 FEET TO THE SOUTH LINE OF LOT 4, SAID BURCH ADDITION; THENCE NORTH 84°07'00" WEST ALONG THE SOUTH LINE OF LOTS 4 AND 10 A DISTANCE OF 215.08 FEET TO THE EAST RIGHT-OF-WAY LINE OF WALL AVENUE (SR-204); THENCE NORTH 00°58'00" EAST ALONG SAID RIGHT-OF-WAY LINE A DISTANCE OF 195.08 FEET TO THE NORTH LINE OF LOT 13, SAID BURCH ADDITION; THENCE SOUTH 84°07'00" EAST ALONG THE NORTH LINE OF LOTS 13, 14 AND 15, SAID BURCH ADDITION A DISTANCE OF 199.88 FEET TO THE NORTHWEST CORNER OF SAID LOT 15; THENCE SOUTH 05°53'00" WEST ALONG THE EAST LINE OF SAID LOT 15 EXTENDED A DISTANCE OF 145.45 FEET TO THE NORTH LINE OF SAID LOT 4; THENCE SOUTH 84°07'00" EAST ALONG THE NORTH LINE OF SAID LOT 4 A DISTANCE OF 63.35 FEET TO THE POINT OF

CONTAINS 0.908 ACRES, MORE OR LESS

NARRATIVE OF SURVEY:

BENCHMARK ENGINEERING & LAND SURVEYING, LLC WAS RETAINED BY AMIN DHANANI OF HZ PROPS, LLC. TO PERFORM AN ALTA/ACSM SURVEY OF SUBJECT PROPERTY AS SHOWN

THE PLAT OF BURCH ADDITION CONTAINS MANY MATHEMATICAL ERRORS. THE BOUNDARY WAS RETRACED BY USING UDOT RIGHT-OF-WAY PLANS, IN CONJUNCTION WITH NEARBY SURVEYS.

THE BASIS OF BEARINGS FOR THIS SURVEY IS NORTH 89°02'13" WEST BETWEEN THE MONUMENTS FOUND MARKING THE INTERSECTIONS OF 36TH STREET AND LINCOLN AVENUE AND 36TH STREET AND WALL AVENUE AS SHOWN HEREON.

DESCRIPTION: MONUMENT IN THE INTERSECTION OF LINCOLN AVENUE AND 36TH STREET ELEVATION: 4340.06 US SURVEY FEET DATUM: NAVD88 (PER WEBER COUNTY ENGINEER DATA)

MAR 1 0 2015

LIST OF REFERENCED DOCUMENTS

R1) COMMITMENT FOR TITLE INSURANCE ISSUED BY FOUNDERS TITLE COMPANY, DATED OCTOBER 20, 2014, AS REFERENCE NO. Fd51849.

36th STREET

- R2) SURVEY PERFORMED BY DALE J. ROBINSON (SUNRISE ENGINEERING INC.), ON FILE WITH THE OFFICE OF THE WEBER COUNTY SURVEYOR AS FILE NO. 003072.
- R3) SURVEY PERFORMED BY GARY J. NEWMAN (GREAT BASIN ENGINEERING, INC.), ON FILE WITH THE OFFICE OF THE WEBER COUNTY SURVEYOR AS FILE NO. 000621.
- R4) BURCH ADDITION SUBDIVISION, ON FILE WITH THE OFFICE OF THE WEBER COUNTY R5) RIGHT-OF-WAY PLANS FOR RIVERDALE ROAD (SR-26), PROJECT NO. SP-0026(4)0, ON
- FILE WITH THE OFFICE OF THE UTAH DEPARTMENT OF TRANSPORTATION. R6) RIGHT-OF-WAY PLANS FOR WALL AVENUE, PROJECT NO. SP1596, ON FILE WITH THE

GENERAL NOTES

VICINITY MAP

THIS SURVEY IS BASED UPON THE COMMITMENT FOR TITLE INSURANCE ISSUED BY

OFFICE OF THE UTAH DEPARTMENT OF TRANSPORTATION.

DESCRIPTIONS AND QUESTIONS AS TO UNDERLYING FEE OWNERSHIP, JUNIOR AND SENIOR RIGHTS OF OWNERSHIP PERTAINING TO ADJOINING PROPERTIES, ARE NOT ADDRESSED ON OR BY THIS MAP. THE INFLUENCE OF OTHER DOCUMENTS COULD RESULT IN THE VARIANCE OF PROPERTY LINES AS SHOWN HEREON.

3) NOTES PERTAINING TO EXCEPTIONS TO COVERAGE, SCHEDULE B OF REFERENCED PRELIMINARY REPORT:

ITEMS 1-17 NOT ADDRESSED BY THIS SURVEY

ENTRY NO.: 2413464

ITEM [18] EASEMENT AND CONDITIONS CONTAINED THEREIN: GRANTEE: UTAH DEPARTMENT OF TRANSPORTATION

ITEM 19 EASEMENT AND CONDITIONS CONTAINED THEREIN: GRANTEE: UTAH DEPARTMENT OF TRANSPORTATION RECORDED: MAY 22, 2009

ENTRY NO.: 2413465 ITEM 20 LEASE

LESSEE: REAGAN OUTDOOR ADVERTISING ENTRY NO.: 1219896

BOOK/PAGE: 1658/1489

DOCUMENTS FURNISHED AND UTILIZED IN THE PERFORMANCE OF THIS SURVEY ARE AS

COMMITMENT FOR TITLE INSURANCE ISSUED BY FOUNDERS TITLE COMPANY, DATED OCTOBER 20, 2014, AS REFERENCE NO. Fd51849

SURVEY NOTES

OCCUPATION LINES AND A BUILDING ENCROACHMENT APPEAR TO HAVE BEEN IN PLACE FOR OVER 20 YEARS. BOUNDARY BY ACQUIESCENCE MAY HAVE TAKEN PLACE. CULINARY WATER LINES HAVE NOT BEEN SHOWN ON THIS SURVEY AS PINEVIEW WATER SYSTEMS DOES NOT KEEP UTILITY LOCATION MAPS ON FILE.

LEGEND AND ABBREVIATIONS:

-63	STREET MON. (FOUND)	RIGHT-OF-WAY LINE
中	STREET MON. (NOT FOUND)	CURB & GUTTER
.	PROPERTY LINE	
0	PROPERTY CORNER (AS NOTED)	
	ADJACENT PL	
S	SANITARY SEWER MANHOLE & PIPE SS SS	
0	STORM DRAIN MANHOLE & PIPE SD ———————————————————————————————————	
_	OVERHEAD POWER LINE	

MAJOR CONTOUR LINE

ABBREVIATIONS: SS SANITARY SEWER SD STORM DRAIN MH MANHOLE

SURVEY

ALTA/ACSM LAND TITLE

PROP(3940 30UTh

1411167

7

SVA.01