
EDGEWOOD ESTATES PHASE 3

PART OF THE SOUTHWEST 1/4 OF SECTION 35, T7N, R2W, SLB&M

FARR WEST CITY, WEBER COUNTY, UTAH



ADDRESS TABLE					
LOT	ADDRESS				
LOT R-43	2235 NORTH 2518 WEST				
LOT R-44	2251 NORTH				
LOT R-45	2265 NORTH				
LOT R-46	2283 NORTH				
LOT R-47	2268 NORTH				
LOT R-48	2254 NORTH				
LOT R-49	2238 NORTH 2442 WEST				
LOT R-50	2489 WEST				
LOT R-51	2461 WEST				
LOT R-52	2433 WEST				

JUN 22 2015 005251

NARRATIVE: THE PURPOSE OF THIS SURVEY WAS TO CREATE A 10 LOT SUBDIVISION AS SHOWN AND DESCRIBED HEREON. THE SURVEY WAS ORDERED BY VALEO MANAGEMENT. THE CONTROL USED TO ESTABLISH THE BOUNDARY WAS THE EXISTING WEBER COUNTY SURVEY MONUMENTATION SURROUNDING SECTION 35, TOWNSHIP 7 NORTH, RANGE 2 WEST OF THE SALT LAKE BASE AND MERIDIAN. THE PLAIN CITY IRRIGATION CO. PROPERTY WAS DETERMINED BY PHYSICAL MEASUREMENT AND CO-INCIDES WITH MEASUREMENTS REPRESENTED IN THE FARR WEST FARMS SUBDIVISION #3. THE BASIS OF BEARING IS THE WEST LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 35 WHICH BEARS NORTH 1.00'00" EAST WEBER COUNTY GRID BEARING.

SOUTHWEST CORNER SEC 35

T7N, R2W, SLB&M WEBER COUNTY

SURVEYOR BRASS CAP MONUMENT

SET IN 1972, GOOD CONDITION

1. UTILITY EASEMENTS ARE INDICATED BY DASHED LINES. WIDTHS AS NOTED. 2. ALL EASEMENTS TO BE USED FOR IRRIGATION WATER LINES, DRAINAGE, SANITARY AND STORM SEWER, POWER LINES, TELEPHONE LINES AND OTHER PUBLIC UTILITIES. 3. #5 REBAR WITH CAP SET AT BACK LOT CORNERS. COPPER RIVET TO BE SET IN CURB AT LOT LINE

4. ZONING: R-15 BUILDING SETBACK: 30' REAR, 30' FRONT, 10'-14' ALT. SIDE YARD, 30' CORNER LOT STREET SIDE, 15' CORNER INTERIOR SIDE. 5. "NOTICE TO PURCHASERS OF RESTRICTED "R" LOTS": LOTS DESIGNATED BY THE LETTER "R" BEFORE THE LOT NUMBER ARE RESTRICTED LOTS AND BASEMENTS ARE RESTRICTED TO 24" MAXIMUM DEPTH BELOW TOP BACK OF CURB ELEVATION. WINDOW WELLS AND HOME ENTRANCES

TO BE LOCATED A MIN. OF 1.0' ABOVE THE TOP BACK OF CURB ELEVATION. LOT FRONTAGE IS


WEBER COUNTY SECTION CORNER MONUMENT (AS NOTED)

CENTER LINE MONUMENT (TO BE INSTALLED) 5/8'X24' REBAR AND CAP MARKED 'GARDNER ENGINEERING'

CENTER LINE OF RIGHT OF WAY

10' PUBLIC UTILITY EASEMENT **BOUNDARY LINE**

ZONING: R-15 **BUILDING SETBACKS:** 30' REAR AND REAR 10'-14' ALT .SIDE YARD 30' CORNER LOT STREET SIDE 15' CORNER LOT INTERIOR SIDE



DEVELOPER: VALEO MANAGEMENT 1080 SOUTH DEPOT DR. OGDEN, UTAH 84404

FARR WEST CITY ATTORNEY

TO BE GRADED AT MIN. OF 3.0 % FROM FRONT OF HOUSE TO R.O.W.

CAP MONUMENT SET IN

1981 GOOD CONDITION

I HAVE EXAMINED THE FINANCIAL GUARANTEE AND OTHER DOCUMENTS ASSOCIATED WITH THIS SUBDIVISION PLAT AND IN MY OPINION THEY CONFORM WITH THE FARR WEST CITY ORDINANCE APPLICABLE THERETO AND NOW IN FORCE AND AFFECT.

FARR WEST CITY PLANNING COMMISSION

THIS IS TO CERTIFY THAT, THIS SUBDIVISION PLAT WAS DULY APPROVED BY THE FARR WEST CITY PLANNING COMMISSION ON THE 17th DAY OF Tane 2015

FARR WEST CITY ENGINEER

I CERTIFY THAT I HAVE EXAMINED THIS PLAT AND FIND IT TO BE CORRECT AND IN ACCORDANCE WITH INFORMATION ON FILE IN THIS OFFICE.

FARR WEST CITY COUNCIL ACCEPTANCE


THIS IS TO CERTIFY THAT THIS SUBDIVISION PLAT, THE DEDICATION OF STREETS AND OTHER PUBLIC WAYS AND FINANCIAL GUARANTEE OF PUBLIC IMPROVEMENTS ASSOCIATED WITH THIS SUBDIVISION THEREON ARE HEREBY APPROVED AND ACCEPTED BY THE CITY COUNCIL OF FARR WEST CITY, UTAH

ACKNOWLEDGMENT

STATE OF UTAH COUNTY OF WEBER

__, 2015, PERSONALLY ON THIS 320 DAY OF NUNE APPEARED BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC IN AND FOR SAID COUNTY OF WEBER, IN SAID STATE OF UTAH, BRETT SATTERTHWAITE, BEING BY ME DULY SWORN, ACKNOWLEDGED TO ME THAT HE IS PRESIDENT OF VALEO MANAGEMENT AND THAT HE SIGNED THE ABOVE OWNER'S

DEDICATION IN BEHALF OF SAID CORPORATION, AND HE ACKNOWLEDGED TO ME THAT SAID




SURVEYOR'S CERTIFICATE

I, KLINT H. WHITNEY, DO HEREBY CERTIFY THAT I AM A LICENSED PROFESSIONAL LAND SURVEYOR IN THE STATE OF UTAH AND THAT I HOLD CERTIFICATE NO. 8227228 IN ACCORDANCE WITH TITLE 58, CHAPTER 22, OF THE PROFESSIONAL ENGINEERS AND LAND SURVEYORS ACT; I FURTHER CERTIFY THAT BY AUTHORITY OF THE OWNERS I HAVE COMPLETED A SURVEY OF THE PROPERTY DESCRIBED ON THIS SUBDIVISION PLAT IN ACCORDANCE WITH SECTION 17-23-17 AND HAVE VERIFIED ALL MEASUREMENTS; THAT THE REFERENCE MONUMENTS SHOWN ON THIS RECORD OF SURVEY PLAT ARE LOCATED AS INDICATED AND ARE SUFFICIENT TO RETRACE OR REESTABLISH THIS SURVEY; AND THAT THE INFORMATION SHOWN HEREIN IS SUFFICIENT TO ACCURATELY ESTABLISH THE LATERAL BOUNDARIES OF

SIGNED THIS 3PD DAY OF JUNE

THE HEREIN DESCRIBED TRACT OF REAL PROPERTY.



PHASE 3 BOUNDARY DESCRIPTION

A PART OF THE SOUTHWEST QUARTER OF SECTION 35 TOWNSHIP 7 NORTH RANGE 2 WEST OF THE SALT LAKE BASE AND MERIDIAN.

BEGINNING AT A POINT ON THE NORTH LINE OF SAID SOUTHWEST QUARTER, SAID POINT ALSO BEING THE NORTHEAST CORNER OF LOT 20 OF THE EDGEWOOD ESTATES SUBDIVISION PHASE 1, BEING LOCATED SOUTH 89° 18'53" EAST 1328.00 FEET FROM THE WEST QUARTER CORNER OF SAID SECTION 35; RUNNING THENCE ALONG THE NORTH LINE OF SAID SOUTHWEST QUARTER SOUTH 89°18'53" EAST 329.50 FEET; THENCE SOUTH 01°30'00" WEST 447.56 FEET; THENCE SOUTH 88°28'14" EAST 85.17 FEET; THENCE SOUTH 01°31'46" WEST 60.00 FEET; THENCE SOUTH 01°27'33" WEST 123.43 FEET TO THE NORTH RIGHT-OF-WAY LINE OF THE PLAIN CITY CANAL CO.; THENCE ALONG SAID NORTH RIGHT-OF-WAY LINE NORTH 88'37'47" WEST 363.90 FEET TO THE EAST BOUNDARY LINE OF EDGEWOOD ESTATES PHASE 1; THENCE ALONG SAID EAST BOUNDARY LINE THE FOLLOWING (5) FIVE COURSES: (1) NORTH 01°27'33" EAST 124.44 FEET: (2) THENCE NORTH 01°31'46" EAST 60.00 FEET: (3) THENCE NORTH 88°28'14" WEST 47.77 FEET; (4) THENCE NORTH 01°31'46" EAST 226.24 FEET; (5) THENCE NORTH 00°41'07" EAST 216.49 FEET TO THE POINT OF BEGINNING. CONTAINS 212,577.40 SQ.FT. OR 4.88 ACRES.


	Curve Table				
Curve #	Length	Radius	Deita	Chord	
C1	16.49	10.50	90.000	N46° 31' 46"E - 14.85	
C2	22.83	25.00	52.330	N24° 38' 09"W - 22.05	
С3	29.39	65.00	25.905	N37° 50' 53"W - 29.14	
C4	94.39	65.00	83.206	N16° 42' 28"E - 86.32	
C5	71.95	65.00	63.421	S89° 58' 43"E - 68.33	
C6	94.83	65.00	83.590	S16° 28' 22"E - 86.64	
C7	32.37	65.00	28.537	S39° 35' 27"W - 32.04	
C8	22.83	25.00	52.330	S27° 41' 40"W - 22.05	
C9	16.49	10.50	90.000	S43° 28' 14"E - 14.85	
C10	322.94	65.00	284.660	N88° 28' 14"W - 79.44	


OWNER'S DEDICATION

I THE UNDERSIGNED OWNER OF THE HEREON DESCRIBED TRACT OF LAND, HEREBY SET APART AND SUBDIVIDE THE SAME INTO LOTS, PARCELS AND STREETS AS SHOWN ON THIS PLAT AND NAME SAID TRACT:

EDGEWOOD ESTATES PHASE 3

AND HEREBY DEDICATE, GRANT AND CONVEY TO FARR WEST CITY, WEBER COUNTY, UTAH ALL THOSE PARTS OR PORTIONS OF SAID TRACT OF LAND DESIGNATED AS STREETS, THE SAME TO BE USED AS PUBLIC THOROUGHFARES FOREVER, AND ALSO GRANT AND DEDICATE A PERPETUAL EASEMENT OVER, UPON AND UNDER THE LANDS DESIGNATED ON THE PLAT AS PUBLIC UTILITY, STORM WATER DETENTION PONDS, DRAINAGE, CANAL MAINTENANCE AND CANAL SLOPE EASEMENTS, THE SAME TO BE USED FOR THE INSTALLATION, MAINTENANCE AND OPERATION OF PUBLIC UTILITY SERVICE LINES, STORM DRAINAGE FACILITIES OR FOR THE PERPETUAL PRESERVATION OF WATER DRAINAGE CHANNELS IN THEIR NATURAL STATE WHICHEVER IS APPLICABLE AS MAY BE AUTHORIZED BY FARR WEST CITY, UTAH, WITH NO BUILDINGS OR STRUCTURES BEING ERECTED WITHIN







5150 SOUTH 375 EAST OGDEN, UT OFFICE: 801.476.0202 FAX: 801.476.0066

COUNTY RECORDER

ENTRY NO. _____ FEE PAID ____ FILED FOR RECORD AND RECORDED IN_____ BOOK ___ OF OFFICIAL RECORDS, PAGE ___. RECORDED

COUNTY RECORDER

DEPUTY